

# NOTICE TO MARINERS

## DOGGER BANK WIND FARM

### DOGGER BANK OFFSHORE WIND FARM

DATE OF ISSUE:	05/09/2025
NOTICE TO MARINER NUMBER	LF700013-IAC-DOG-NOT-0003

### Dogger Bank C IAC Post Lay Burial (PLB)

LOCATION DESCRIPTION		Dogger Bank C Offshore Windfarm
COORDINATES WGS 84	DBA OWF	See Table 1 below
START DATE/TIME		17/09/2025
END DATE/TIME		08/10/2025

### Description of Hazard/Operation

The Trenching Support Vessel, **Assister**, will perform Inter Array Cable Post-Lay Burial operations in Dogger Bank C Offshore Windfarm Area.

The campaign will commence on the 17<sup>th</sup> of September 2025 and continue until approximately 8<sup>th</sup> of October 2025. The works will be continuous, 24 hours a day. Charts of the DBC array area are provided below.

The operations include the post lay burial operations for part of the array cable routes, by means of jetting in order to protect the inter-array cables.

During operations, the **Assister** will be restricted in its ability to manoeuvre as defined under COLREGs (International Regulations for Preventing Collisions at Sea 1972) and will display the appropriate day shapes and lights. The vessel will also transmit an Automatic Identification System (AIS) message.

It is requested that all vessels maintain a minimum of 1.5Nm separation distance from the TSV and pass at reduced speed. Fishing gear or other equipment with seabed intervention should not be deployed when approaching the working corridor.


### Contact Details

Marine Coordination Contact	Duty Marine Coordinator Tel: +44 (0) 7586 332078 <a href="mailto:gm_dbmcc@equinor.com">gm_dbmcc@equinor.com</a>
Fisheries Liaison Officer (FLO) CONTACT	Alex Winrow-Giffin, Brown & May Marine Ltd <a href="mailto:Alex@brownmay.com">Alex@brownmay.com</a> Tel: 01379 870181 Mob: 07760 160039 Zoë Lawrence - Brown & May Marine Ltd <a href="mailto:zoe@brownmay.com">zoe@brownmay.com</a> Mob: 07923 138175
Vessel Shore Contact	Bart van Dun (DEME HSE Manager) Mobile: +31 6 38 68 59 48 Email: <a href="mailto:BAVD@deme-group.com">BAVD@deme-group.com</a>

# NOTICE TO MARINERS


## DOGGER BANK WIND FARM

### Supporting Information

Vessel – Assister		Contact Details	
		Call Sign	OYUJ2
		MMSI / IMO	219699000 / 9193783
		Vessel Details	
		Length / Beam	90.3m / 23m
		Draft	7.8m
		Vessel Contact	Bridge: +45 32 22 24 02

**Table1:** Coordinates for DBC Construction area

COORDINATES WGS 84	DBC IAC array area	Latitude		Longitude	
		55°08.119'N		002°32.765'E	
		55°08.152'N		002°45.781'E	
		54°58.196'N		003°00.170'E	
		54°56.238'N		003°00.169'E	
		54°56.191'N		002°32.921'E	



**Figure 1:** Fig 1 Dogger Bank C OWF IA Cable Layout